

Central Water & Electric Utility Services

P.O. BOX 1409
 POLK CITY, FL 33868 US
 8637389215
 sjones7285@aol.com


Estimate

ADDRESS
 Blue Cypress mhp
 13801 US-441
 OKEECHOBEE, FL 34974

SHIP TO
 Blue Cypress mhp
 13801 US-441
 OKEECHOBEE, FL 34974

ESTIMATE #	DATE
1700	11/07/2023

SALES REP
 S JONES



DATE	ACTIVITY	DESCRIPTION	QTY	RATE	AMOUNT
	Repair & Maintenance	Repair & Maintenance BLUE CYPRESS GOLF & RV RESORT HYDROPNEUMATIC TANK INSTALLATION ONLY INCLUDES THE FOLLOWING: 1 FREIGHT PICK UP TANK JACKSONVILLE & DELIVER TO SITE 1 REMOVAL OF OLD TANK OFF SITE 2 4" FLANGE PACK 1/8" FULL FLANGE GASKET - ZINC BOLTS 1 Rubber lining for tank to sit on saddles 1 Crane for removing and setting tank 1 1-1/2" ss Pressure & vacuum relief valves 1 1" Air release and fittings 3 1" ss ball valve & fittings 2 2" ss ball valve - nipples and drain piping 6 Insta-Flange Adapter 6" Ductile Iron Pipe 1 6" DI PIPE 1 Drill and tap saddles - red heads 1 Remove and reinstall compressor. NOTE: THE NEW FLANGES CANNOT BE MANUFACTURED AT THE SAME HEIGHT. OLD FLANGES WERE 1-5/8 FROM TANK TO FLANGE.	1	19,607.00	19,607.00

DATE	ACTIVITY	DESCRIPTION	QTY	RATE	AMOUNT
		MINIUMUM OF NEW TANK IS 6". WE WILL NEED TO REPIPE THE INFLUENT LINE INTO THE TANK. ADDITIONALLY, THE PRESSURE RELIEF VALVE ON THE TANK ORIGINALLY WAS BRASS WHICH HAS LEAD. NEW INSTALLATION MUST BE LEAD FREE AND FRANKLY ARE A RIDICULOUS COST BUT MUST BE INSTALLED.			
				SUBTOTAL	19,607.00
				TAX	0.00
				TOTAL	\$19,607.00

Accepted By

Accepted Date