



Mohawk Construction, Inc.

1307 SW 18th Terr
Okeechobee, FL 34974

Estimate

DATE	ESTIMATE NO.
5/28/2024	939

NAME / ADDRESS
Blue Cypress Golf & RV Resort Bill Cypress 517-462-2707

P.O. NO.	TERMS	PROJECT

DESCRIPTION	QTY	COST	TOTAL
Blue Cypress Golf & RV Resort- Drainage Repair / Replacement.			
Machinery / Labor / Mobilization / 300' of double wall 36" HDPE culverts - Remove asphalt over existing drainage pipes. Remove existing pepper trees, barbwire fencing, oak and palm tree stumps and existing culverts to be pile up onsite. New drainage pipe's will be installed at the same elevation as existing drainage pipe's. Pipe trench will be backfilled with existing dirt and compacted. Pipe Joints will be wrapped and tied in fabric.	1	45,000.00	45,000.00
Estimated 3 loads of 57 stone Pipe bedding. YOU WILL ONLY BE CHARGED FOR THIS ITEM IF IT IS NEEDED. Price per load is \$1,500 delivered and installed.			0.00
<p>Excluded</p> <p>1. If any clean fill dirt is needed to back fill drainage pipe it will be additional cost. This would only occur if we encounter non suitable materials for backfill of new drainage pipe's.</p> <p>2. Well point de-watering.</p> <p>3. No sod, concrete or pavement is included in estimate at this time.</p> <p>4 Debris can be hauled offsite and disposed for an additional price.</p>			
		TOTAL	\$45,000.00

Walter Bost
Walter Bost